

In silico Homology Modeling and Epitope Prediction of NadA as a Potential Vaccine Candidate in *Neisseria meningitidis*

Narjes Shahsavani¹, Mohammad Hasan Sheikhha¹, Hassan Yousefi², Fatemeh Sefid^{3*}

1. Shahid Sadoughi University of Medical Sciences and Health Services, Yazd, Iran.

2. Department of Medical Genetics, School of Medicine, Tehran University of Medical Sciences, Tehran, Iran.

3. Department of Biology, Science and Arts University, Yazd, Iran.

Submitted 5 July 2017; Accepted 24 January 2018; Published 10 February 2018

Neisseria meningitidis is a facultative pathogen bacterium which is well founded with a number of adhesion molecules to facilitate its colonization in human nasopharynx track. *Neisseria meningitidis* is a major cause of mortality from severe meningococcal disease and septicemia. *Neisseria meningitidis* adhesion, NadA, is a trimeric autotransporter adhesion molecule which is involved in cell adhesion, invasion, and antibody induction. It is identified in approximately 50% of *N. meningitidis* isolates, and is established as a vaccine candidate due to its antigenic effects. In the present study, we exploited bioinformatics tools to better understand and determine the 3D structure of NadA and its functional residues to select B cell epitopes, and provide information for elucidating the biological function and vaccine efficacy of NadA. Therefore, this study provided essential data to close gaps existing in biological areas. The most appropriate model of NadA was designed by SWISS MODEL software and important residues were determined using the subsequent epitope mapping procedures. Locations of important linear and conformational epitopes were determined and conserved residues were identified to broaden our knowledge of efficient vaccine design to reduce meningococcal infection in population. These data now provide a theme to design more broadly cross-protective antigens.

Key words: *Neisseria meningitidis*, NadA, epitope prediction, 3D structure

Neisseria meningitidis is a capsulate gram negative diplococcus which can colonize the upper respiratory tract of humans. It is the major responsible of pyogenic meningitis in children and young adults which can cause their death during a short time despite the advances in drug discovery (1-3). It is reported that the number of patients with

meningococcal disease varies from 0.5 to 10 per 100,000 persons each year. Relatively, the patient's number can surge to 15 and 400 per 100,000 during epidemics. 5 to 15% of the patients die from the disease, and 25% of survivors suffer from neurological problems (4-6). Therefore, *N. meningitidis* should be accounted as a disastrous

*Corresponding author: Department of Biology, Science and Arts University, Yazd, Iran.
Email: sefid@shahed.ac.ir

pathogen. It was reported that in special occasions the bacterium is able to move throughout the nasopharynx mucosal layer which can inevitably result in an invasive meningococcal disease including septicemia, and fulminate meningitidis (6, 7). To induce disease, the bacterium needs a broad number of properties leading to colonization as well as invasion to the mucosal barriers, and eventually blood, resulting in septicemia followed by interaction with brain cell microvessels, and blood- brain barrier penetration (8-10). Adhesion-associated properties are due to type IV pili (Tfp), and the non-pilus adhesins which comprise opacity proteins Opa and Opc, and the auto transporter proteins App (adhesion penetration protein), NhhA (Neisseria hia homolog), and NadA (Neisseria adhesin A) (9, 11).

There were numerous attempts to vaccine investigation. The first phases of efficient vaccines in adults but not in children were based on purified polysaccharides of four highly virulent serogroups of *N. meningitidis* (A, C, Y, and W-135). The next efforts were glycoconjugate- based vaccines against C serogroup which were highly successful in disease eradication caused by the mentioned serogroup in infants, children, and adults with 90% confidence. It is of paramount to approach surface exposed proteins in vaccine generation. These vaccines not only induce bactericidal antibodies, but may also eliminate further meningococcal diseases. Mentioned vaccines have been utilized in some countries but there are obstacles which should be tackled. The most important one is their weakness in supporting provision against heterologous strains due to the high sequence variability of protein antigens (12-15).

In this study we focused on NadA, a potential virulence factor, an adhesion molecule, and vaccine candidate. NhhA and NadA are members of the oligomeric coiled-coil adhesion (Oca) family, also named trimeric auto transporters. NadA contributes to bacterial virulence due to its expression in near

50% of disease-associated isolates (8). More than 80% of isolates in hyper virulent lineages have nadA gene, and about half of the meningococcal isolates generate NadA (16, 17). NadA antigen is also reported to be present in 52 out of 53 strains of hypervirulent lineage electrophoretic types (18). Statistical association studies confirm this fact. In disparate geographical locations and time periods, isolates from the same clonal features have similar profiles for this antigen (19). Immunogenic nature of NadA is considerable, while it stimulates the immune system to produce high levels of bacterial antibodies and can be recognized by children's serum antibodies after invasive meningococcal disease (IMD) (20, 21). The gene encoding NadA is associated with strains that belong to three of the four hypervirulent serogroup B (22, 23). Lineages amino acids in C-terminal part have high similarity with that of the Yersinia adhesion YadA with special structure (17, 24). The rate of nadA expression differs among isolates, and can be up to 100-fold. Moreover, it will be over expressed under *in vivo* condition due to the existence of special signals which are associated with the appropriate niche (25, 26). NadA sequences are genetically divided into two categories with 45-50% amino acid identity. The first group consists of NadA1, NadA2, and NadA3 which are the most prevalent variants. It is exhibited that their sequence identity rate is 95%, and are cross-reactive from an immunogenic perspective. NadA4, NadA5, and NadA6 are members of the second group which are not common variants (24). In this report, we employed bioinformatics tools for 3D structure investigation regarding the fact that experimental determination is a considerable challenge since it is time-consuming, and its failure rate is relatively high (27). The first step in drug designing is *in silico* study to evaluate capability of candidate molecules. *In silico* studies can be used to determine the target structures for possible binding sites, identify candidate molecules, evaluate their

capability to be considered as a drug, dock these molecules with the target, rank them according to their binding affinities, and refine structures to improve binding characteristics (28).

For outer membrane proteins such as NadA, purification and crystallization are cumbersome problems in addition to mentioned obstacles. Taken together, bioinformatics utilization can be more advantageous, and structure investigation is one of the wide applications of these tools in antigen determination and epitope mapping for designing new generation and highly effective vaccines.

Materials and methods

Sequence availability, homology search and alignment

NadA protein sequence with ACM47292.1 accession number containing 362 amino acids was obtained from NCBI at <http://www.ncbi.nlm.nih.gov/protein>, and saved in FASTA format for the further analysis. <http://blast.ncbi.nlm.nih.gov/Blast.cgi> was utilized for mentioned protein BLAST against non-redundant protein database as well as obtaining probable putative conserved domains of the protein. PRALINE (29) at <http://www.ibi.vu.nl/programs/pralinewww/> was used for generation of alignments. Alignments are used to investigate the conservancy of the protein amino acids among various strains. In this regard, suitable vaccine candidates are those effective against all strains of a given pathogen. Conservancy of the protein amino acids among bacteria other than *Neisseria* implies probable cross-reactivity levels.

Homologous structure search

To provide template structures the query protein sequence was used as an input data for the PSI-BLAST against protein data bank (PDB) at <http://blast.ncbi.nlm.nih.gov/Blast.cgi>.

General sequence characteristics

Protein sequence properties including molecular weight, theoretical pI, amino acid composition, total number of negatively and

positively charged residues, instability index, and aliphatic index were obtained from an online software at <http://expasy.org/tools/protparam.html>, Protparam (30).

Topology prediction

PREDTMBB server (<http://biophysics.biol.uoa.gr/PRED-TMBB/>) was recruited for transmembrane β -strands prediction in protein sequences. The web server could find the topology of the loops in addition to localizing the transmembrane strands. Prediction of hydrophobic transmembrane regions in a protein sequence generates probable β -barrels that could help determine the 3D protein structure. Topology prediction servers predict the probability of a particular residue to be located either inside or outside of the membrane. Transmembrane helix and signal peptides are not suitable regions as B cell epitope. SPOCTOPUS (31) at <http://octopus.cbr.su.se/> was also employed to determine membrane protein topology and signal peptides.

Secondary structure prediction

Self-optimized prediction method (SOPM) has been described to improve the efficiency of protein secondary structure prediction. The secondary structure of protein including helix, sheet, turn, and coil parameters was predicted at http://npsa-pbil.ibcp.fr/cgi-bin/npsa_automat.pl?page=npsa_sopma.html.

Modeling methods

Phyre2 (32) at <http://www.sbg.bio.ic.ac.uk/phyre2/html/page.cgi?id=index> uses hidden markov model alignments through HH search to notably enhance accuracy of alignment and detection rate. To model regions with no detectable homology, phyre2 integrates a new ab initio folding simulation called Poing.

The SWISS- MODEL workspace at <http://swiss-model.expasy.org/> is a web-based incorporated service specialized in protein structure homology modelling.

Model evaluation

All 3D models of the protein built, were qualitatively estimated by GMQE and QMEAN4 scores. Qualitative evaluation of 3D models was done by ProSA at <https://prosa.services.came.sbg.ac.at> (33). ProSA specifically faces the needs confronted in the authentication of protein structures acquired from X-ray analysis, NMR spectroscopy, and hypothetical estimations.

Rampage (34) at <http://mordred.bioc.cam.ac.uk/rapperrampage.php> was also employed for estimation of model quality using Ramachandran plot which is an algorithm for atomic level, high-resolution protein structure improvement. It can begin from either C-alpha trace, main-chain model or full-atomic model. ModRefiner (35) at <http://zhanglab.ccmb.med.umich.edu/ModRefiner/> is another algorithm with functions similar to Rampage.

Ligand binding site prediction

Cofactor at <http://zhanglab.ccmb.med.umich.edu/COFACTOR/> is a structure-based method for biological purpose notation of protein molecules. Important amino acids involved in ligand binding site are predicted by this server.

Functional and structural critical residues identification

Functional conserved residue allows more realism and robustness in the description of protein binding surfaces and epitope prediction. There are several ways to functionally and structurally annotate/predict important residues.

In this study, InterProSurf at <http://curie.utmb.edu/pattest9.html> was employed to predict functional sites on protein surface using patch analysis. NadA structure determined by previous strategies, served as an input file for this server. Conseq (36) at <http://conseq.tau.ac.il/> utilized NadA sequence as an input. The software parameters were set as follows: PSI-BLAST for five iterations against Uniprot database with E-value of 0.01, and maximum likelihood (ML) as a method of calculating amino acid conservation score.

Single-scale amino acid properties assay

Segments within NadA sequence that are likely to be antigenic were predicted using Bcepred at <http://www.imtech.res.in/raghava/bcepred> with accuracy of 58.7%. This server predicts B-cell epitopes using single of the physico-chemical properties (hydrophilicity, flexibility, mobility, accessibility, polarity, exposed surface and turns) or combination of them. Parameters such as hydrophilicity, flexibility, accessibility, turns and antigenic propensity of polypeptide have been correlated with the location of B cell epitopes.

Cleft and cavity analysis

Profunc at <http://www.ebi.ac.uk/thornton-srv/databases/profunc/> was used to predict clefts and grooves in the protein surface. Depth of clefts and amino acids located within the clefts are predictable by this software.

Sequence-based B cell epitope prediction

Two servers were used to ascertain B cell epitopes in NadA. ABCpred at <http://www.imtech.res.in/raghava/abcpred/> was used to predict B cell epitope in an antigen sequence.. Window length used for prediction with 0.80 threshold set as 16-mer and overlapping filter was on. BepiPred at <http://www.cbs.dtu.dk/services/BepiPred/> was used to predict the location of linear B-cell epitopes.

Structure-based B cell epitope prediction

NadA 3D structure served as an input file for servers predicting B cell epitopes based on 3D structure of a given protein. EPCES at <http://sysbio.unl.edu/EPCES/> was used to predict antigenic epitopes on protein surfaces. Ellipro at <http://tools.immuneepitope.org/tools/ElliPro/tutorial.jsp> was used to predict linear and discontinuous antibody epitopes.

Pocket and binding site detection

GHECOM (Grid-based HECOMi finder) at <http://strcomp.protein.osaka-u.ac.jp/ghecom/> was used to find multi-scale pockets on protein surfaces.

Results

Sequence availability and alignments

NadA protein sequence with accession number ACM47292.1 and GI:222159579 was obtained, and saved in FASTA format. BLAST search revealed numerous hits to the NadA subunit sequence. Putative conserved domains have been detected. Most of the sequences belonged to YadA super family Protein. Putative conserved domains within this sequence are shown in Figure 1.

Template search

The first illustrated result of PSI-BLAST against PDB data bank with 46% identity, 26%

query coverage, 77.4 max score and 77.4 total score, chain A, crystal structure of *Neisseria Meningitidis* trimeric autotransporter and vaccine antigen NadA with "4CJD" PDB ID code was opted as template for homology and other modeling strategies. With regard to E-value, max score identification was also influenced by query coverage and max identity. An appropriate hit for template usage is the one with lower E-value, higher query coverage, and max identity. Alignment strategy has been utilized to manifest sequence similarities between the s elected target




Fig. 1. NadA conserved domain. YadA- anchor superfamily is shown.




Fig. 2. 2D topology model of NadA predicted by TMBBPred server. Residues from 34-42, 89-97, 104-110 and 217-223 are transmembrane regions.

and other probable templates. Alignment provides a golden opportunity to apply the predicted model to other NadA proteins from other close species.

Sequence characteristics

Physical and chemical properties of the selected sequence were predicted. NadA consists of 57 negatively charged residues (Asp+Glu), and 41 positively charged residues (Arg+Lys). Parameters such as molecular weight, theoretical pI (isoelectric point), instability index, aliphatic index, and grand average of hydropathicity which indicate the solubility of the proteins (positive GRAVY

(hydrophobic), negative GRAVY (hydrophilic)) are summarized in Table1.

Secondary structure and topology assessment

A 2D topology model of NadA was built based on predicted inside, transmembrane, and outside regions of the protein (Fig 2). Coil, helix, and strands are components constituting secondary structure of the protein. The secondary structure can be used to confirm the tertiary structures. Attributions of the secondary structure components in the protein are alpha helix (67.13%), extended strand (11.6%), beta turn (6.35%), and random coil

Table1. physical and chemical parameters of NadA.

Number of amino acids	362				
Molecular weight	37753.74				
Theoretical pI	4.79				
Amino acid composition	Ala (A)	71	19.6%/ Arg (R)	5	1.4%
	Asn (N)	24	6.6%/ Asp (D)	29	8.0%
	Cys (C)	1	0.3%/ Gln (Q)	8	2.2%
	Glu (E)	28	7.7%/ Gly (G)	22	6.1%
	His (H)	3	0.8%/ Ile (I)	16	4.4%
	Leu (L)	19	5.2%/ Lys (K)	36	9.9%
	Met (M)	1	0.3%/ Phe (F)	11	3.0%
	Pro (P)	2	0.6%/ Ser (S)	14	3.9%
	Thr (T)	38	10.5%/ Trp (W)	1	0.3%
	Tyr (Y)	6	1.7%/ Val (V)	27	7.5%
	Pyl (O)	0	0.0%/ Sec (U)	0	0.0%
Total number of negatively charged residues (Asp +Glu)	57				
Total number of positively charged residues (Arg +Lys)	41				
Atomic composition	Carbon	C	1634		
	Hydrogen	H	2640		
	Nitrogen	N	452		
	Oxygen	O	567		
	Sulfur	S	2		
Formula/Total number of atoms	: C ₁₆₃₄ H ₂₆₄₀ N ₄₅₂ O ₅₆₇ S ₂ / 5295				
Extinction coefficients					
Extinction coefficients are in units of M ⁻¹ cm ⁻¹ , at 280 nm measured in water.					
Ext. coefficient	14440				
Abs 0.1% (=1 g/l) 0.382, assuming all pairs of Cys residues form cystines					
Ext. coefficient	14440				
Abs 0.1% (=1 g/l) 0.382, assuming all Cys residues are reduced					
Estimated half-life	The estimated half-life is: 30 hours				
The N-terminal of the sequence considered is M (Met).					
	(mammalian reticulocytes, in vitro).				
	>20 hours (yeast, in vivo).				
	>10 hours (Escherichia coli, in vivo).				
Instability index	This classifies the protein as stable				
The instability index (II) is computed to be 12.45					
Aliphatic index/Grand average of hydropathicity (GRAVY)	78.95/ -0.337				




Fig. 3. Graphical representation of the most likely topology predicted by SPOCTOPUS. Network output: The two diagrams show the estimated preference for each residue to be located in different structural regions. The top diagram shows the preference of being either in (1) the hydrophobic part of the membrane, 0–13 Å from the membrane center (M), (2) the membrane water-interface, 11–18 Å from the membrane center (I), (3) a close loop region, 13–23 Å from the membrane center (L), (4) a globular region, further than 23 Å from the membrane (G). The bottom diagram shows the estimated preference of a particular residue to be located either on the inside (i) or on the outside (o) of the membrane. The raw data underlying these two plots can be found in the OCTOPUS network file.




Fig. 4. NadA 3D structure model predicted by SWISS MODEL.




Fig. 5. Model validations. Both global and local estimation of the quality of the obtained model are reasonable.




Fig. 6. Model evaluation. (a) Ramachandran plot of final NadA model. Number of residues in favored region: 177 (93.7%). Number of residues in allowed region: 9 (4.6%). Number of residues in outlier region: 3 (1.8%). (b)- Prosa protein structure analysis results. Z score = -4.75. Overall quality of the ultimate model is acceptable.




Fig. 7. NadA ligand binding sites predicted by COFACTOR. NadA structure in contact with peptide ligand from lateral view. Ligand in the space filling model

(14.92%). Transmembrane helix does not have antigenic capability and Spoctopus server results did not detect any such helix (Fig.3).

Homology modeling

Swiss model and phyre2 software were recruited for homology modeling. The former prepared 3 different models, and the latter introduced one model. All of them were selected for further analyses. The identity score was 46%.

Model evaluation

The best 3D model is shown in Figure 4, and model validations are shown in Figure 5. To tackle


a number of problems including model structural distortions, plus steric clashes, unphysical phi/psi angles, and irregular hydrogen bonding (H-bonding) networks, all models were evaluated by Rampage and Prosa servers. Regarding the Ramachandran plot, 93.7% of the residues are in favored regions, and 4.8% are in allowed parts while the mere amount of 1.6% are existing in outlier regions (Fig. 6a). Prosa revealed that the predicted model was among other acceptable proteins with z score = -4.75. (Fig. 6b).

Ligand binding site regions

[illegible]

1	2	3	4	5	6	7	8	9
Variable				Average			Conserved	

- e - An exposed residue according to the neural-network algorithm.
- b - A buried residue according to the neural-network algorithm.
- f - A predicted functional residue (highly conserved and exposed).
- s - A predicted structural residue (highly conserved and buried).
- X - Insufficient data - the calculation for this site was performed on less than 10% of the sequences.



Cofactor results illustrated cooperation of conserved residues in ligand binding site (189, 192, 194, 196, 197, 198, 200, 201, 202, 203, 209, 210, 216) with the highest C score LB which indicates the confidence of predicted binding site. Local similarity (sequence & structure) assessment between template binding site and predicted binding site in the query structure showed score 1.02 (BS-score>1) that represents a significant local match between the predicted and template binding site (Fig. 7).

Functional and structural critical residues

ConSurf and interproSurf annotated functional residues on the 3D structure of NadA. Results are shown in Figures 8a and b, respectively. ConSurf showed that majority of conserved residues are located in C-terminal region and 17 residues are predicted to be functionally important while residues number 245, 259 and 295 are critical from structure perspective. InterproSurf revealed residues number 150,151, 153,154,213,271,272 272,273, 274,275,276,152,155 by auto patch analysis.

Table 2. Bcepred hydrophilicity, accessibility, antigenicity, flexibility and beta turn secondary structure prediction in the protein sequence.

Sequence	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADVEA DDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTFAE ETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETAAGKA EAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLFPQYNVG RFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²
Hydrophilicity	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADV EADDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTF FAEETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETA AAGKAEAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLF QPNVGRFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²
Flexibility	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADVEA DDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTF EETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETAAG KAEAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLFPQYN VGRFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²
Accessibility	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADV EADDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTF TFAEETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETA ETAAGKAEAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLF LPQYNVGRFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²
Turns	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADVEA DDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTF ETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETAAGKA EAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLFPQYNVG RFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²
Exposed Surface	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADVEA DDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTF EETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETAAG KAEAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLFPQYN VGRFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²
Polarity	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADVE ADDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTF FAEETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETA AGKAEAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLFPQ PYNVGRFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²
Antigenic Propensity	MKHFP SKVLTTAILATFCSGALAAATSDDDVKKAATVAIVAAYNNGQEINGFKAGETIYDIGEDGTITQKDATAADVE ADDFKGLGLKKVVTNLTKTVNENKQNVDAKVKAASEIEKLTTKLADTDAALADTDAALDETTNALNKLGENITTF AEETKTNIVKIDEKLEAVADTVDKHAEAFNDIADSLDETNTKADEAVKTANEAKQTAEETKQNVDAKVKAETAAG KAEAAAGTANTAADKAEAAKVTDIKADIATNKADIKN SARIDSLDKNVANLRKETROGLAEQAALSGLFPQYN VGRFNVTAAVGGYKSES AVAIGTGFRFTENFAAKAGVAVGTSSGSSAAYHVG VNYEW ³⁶²

Bold sequences indicate mentioned characteristics in protein sequence.

Single-scale amino acid properties assay

Properties such as hydrophilicity, accessibility, antigenicity, flexibility, and beta turn secondary structure in the protein sequence were predicted by Bcepred server (Table 2). Single-scale amino acid properties were detectable in all sequence length. Query sequence is shown from number 1, and each property has been shown with a distinct color. According to the mentioned characteristics, middle regions of the protein are more likely to have B cell epitope properties. "TSDDDVKKAA", "AEETKTN", "KADEAVKT-ANEAKQTAEETKQNV" residues are capable to be B cell epitopes.

Cleft analysis

ProFunc results showed a location with 12.17Å depth, 57.64% accessible vertices, and 13.66% buried vertices that are the major cleft in NadA.

Prediction of B cell epitopes by integrated strategy

B-cell epitopes are regions on the surface of antigens that are recognized by B-cell receptors or specific antibodies. These epitopes can be categorized into two types: linear (continuous) and conformational (discontinuous) epitopes. Linear B cell epitopes were predicted by Bepipred server (Fig. 9). ABCpred result showed 9 hits of 16 mer peptide sequences as B-cell epitopes with ranking based on scores (Table 3).

The predicted B cell epitopes were ranked according to their score obtained by trained recurrent neural network, with higher score of the peptide corresponding to the higher probability to be an epitope. All shown peptides were above the threshold value chosen (0.80). Linear and discontinuous B cell epitopes were predicted by ElliPro software (Tables 4 and 5). Two discontinuous and 2 linear epitopes with the highest PI (protrusion index) are shown in Figures 10a and 10b.




Fig. 9. Linear B cell epitopes predicted by Bepipred server.

Table3. Predicted linear epitopes (Linear B cell epitope predicted by ABCpred server).

Rank	Sequence	Start position	Score
1	TITQKDATAADVEADD	65	0.95
2	GETIYDIGEDGTITQK	54	0.94
3	DETNTKADEAVKTANE	190	0.92
4	IVKIDEKLEAVADTV	161	0.90
5	TVAIVAAYNNGQEING	35	0.87
6	SGLFQPYNVGRFNVTA	298	0.87
7	AVAIGTGFRFTENFAA	323	0.86
8	YNNGQEINGFKAGETI	42	0.85
9	TTAILATFCSGALAAT	10	0.84
10	DAKVKAAESEIEKLTT	105	0.80

Table 4. Linear Epitopes Predicted by Ellipro.

No.	Start	End	Peptide	Number of residues	Score
1	108	134	VKAAESEIEKLTTKLADTDAALADTDA	27	0.748
2	267	271	AKNSA	5	0.718
3	172	184	ADTVDKHAEAFND	13	0.651
4	221	254	VKAAETAAGKAEAAAAGTANTAADKAEVAACKVTD	34	0.630
5	155	158	EETK	4	0.51

Table 5. Discontinuous Epitopes Predicted by Ellipro

No.	Residues	Number of residues	Score
1	A:V108, A:K109, A:A110, A:A111, A:E112, A:S113, A:E114, A:I115, A:E116, A:K117, A:L118, A:T119, A:T120, A:K121, A:L122, A:A123, A:D124, A:T125, A:D126, A:A127, A:L129, A:A130, A:D131, A:T132, A:D133, A:A134, A:D137, A:T140, A:N141, A:N144, A:A172, A:D173, A:T174, A:V175, A:D176, A:K177, A:H178, A:A179, A:E180, A:A181, A:F182, A:N183, A:D184	43	0.722
2	A:A264, A:A267, A:K268, A:N269, A:S270, A:A271 A:A219, A:V221, A:K222, A:A223, A:A224, A:E225, A:T226, A:A227, A:A228, A:G229, A:K230, A:A231, A:E232, A:A233, A:A234, A:A235, A:G236, A:T237, A:A238, A:N239, A:T240, A:A241, A:A242, A:D243, A:K244, A:A245, A:E246, A:A247, A:V248, A:A249, A:A250, A:K251, A:T253, A:D254, A:Q289, A:G290, A:L291, A:A292, A:E293, A:Q294, A:A295, A:A296, A:L297, A:S298	6	0.702
3	A:A264, A:A267, A:K268, A:N269, A:S270, A:A271 A:A219, A:V221, A:K222, A:A223, A:A224, A:E225, A:T226, A:A227, A:A228, A:G229, A:K230, A:A231, A:E232, A:A233, A:A234, A:A235, A:G236, A:T237, A:A238, A:N239, A:T240, A:A241, A:A242, A:D243, A:K244, A:A245, A:E246, A:A247, A:V248, A:A249, A:A250, A:K251, A:T253, A:D254, A:Q289, A:G290, A:L291, A:A292, A:E293, A:Q294, A:A295, A:A296, A:L297, A:S298	44	0.676
4	A:G147, A:E148, A:I150	3	0.564




Fig10. B cell epitopes with the highest PI score, 2 linear (a) and 2 discontinuous (b) predicted epitopes are represented. Epitopes were mapped on 3D models using Discovery Studio Visualizer 2.5.5 software.



"VKAASEIEIKLTTKLADTDAALADTDA" at position 108- 134 and "AKNSA" at position 267-271 were the best linear epitopes determined by Ellipro.

sites were much higher. This suggests that pockets contribute to the formation of binding sites and active sites of protein. GHECOM results are shown in Figures 11a and b.

Discussion

65 Int J Mol Cell Med Winter 2018; Vol 7 No 1

induces proinflammatory cytokines (9, 11). NadA based vaccines may plummet the meningococcal disease prevalence. Functional blockade of protein may result in bacterial death. It is believed that antibody utilization to target the functional residues results in disruption of bacterial adhesion to the host epithelial cells (12-15). NadA mediated bacterium invasion and adhesion provided us the rational to determine appropriate regions as a vaccine candidates. Bioinformatics tools were exploited to achieve such goal. Additionally, similarity results revealed that NadA sequences were evolutionary conserved in most of the hypervirulent species suggesting that vaccines based on this protein can be effective against other pathogenic serotypes as well as some other Gram-negative bacteria due to the cross- reactivity of their antibodies (19). According to the NadA location and its chemical characteristics (Table 1), it is an outer membrane and acidic protein (PI= 4.79) which are considered as desirable conditions for B cell response induction. Topology predictions revealed that there is not any transmembrane helix in its structure while it is believed that hidden residues such as transmembrane helices are not appropriate B cell epitope candidates.

Building a homology model comprises four main steps: identification of the template, alignment, model building, and quality evaluation (37). These steps has been repeated until a satisfactory model was achieved using SWISS MODEL.

The 3D models estimated qualitatively by two servers revealed that there was a consensus on a single model. QMEAN is a composite scoring function for the estimation of the global and local model quality. The score of a model is also shown in relation to a set of high-resolution PDB structures (Z-score).

Altogether, various methods were employed to provide data on conserved residue detection which are involved in ligand binding and protein- protein

interactions to be used for further investigations such as site directed mutations to improve the knowledge of vaccine and antibody production. In this study, we combined all the data obtained from various servers and software to predict B-cell epitopes. This study provides information on biophysical structure of NadA which was performed by crystallography in previous studies. These data shed light on 3D structure of this critical antigen. The structure presented here reveals functional models that can improve the interpretation of previous studies and facilitate further researches to elucidate thoroughgoing NadA as both an adhesin and a vaccine antigen. These findings now provide a theme to design more broadly cross-protective antigens.

Conflict of interest

Authors declared no conflict of interest.

References

1. Rouphael NG, Stephens DS. *Neisseria meningitidis*: biology, microbiology, and epidemiology. *Methods Mol Biol* 2012;799:1-20.
2. Yazdankhah SP, Caugant DA. *Neisseria meningitidis*: an overview of the carriage state. *J Med Microbiol* 2004;53:821-32.
3. Khater WS, Elabd SH. Identification of Common Bacterial Pathogens Causing Meningitis in Culture-Negative Cerebrospinal Fluid Samples Using Real-Time Polymerase Chain Reaction. *Int J Microbiol* 2016;2016:5 Pages.
4. Gotschlich EC, Liu TY, Artenstein MS. Human immunity to the meningococcus. 3. Preparation and immunochemical properties of the group A, group B, and group C meningococcal polysaccharides. *J Exp Med* 1969;129:1349-65.
5. Jafri RZ, Ali A, Messonnier NE, et al. Global epidemiology of invasive meningococcal disease. *Popul Health Metr* 2013;11:17.
6. Trotter C, Ramsay M, Harrison L. Introduction and epidemiology of meningococcal disease. In: Feavers I, Pollard AJ, Sadarangani M, editors. *Handbook of Meningococcal Disease Management*. Cham: Springer International Publishing; 2016. p. 1-14.
7. Slanina H, Hebling S, Hauck CR, et al. Cell invasion by *Neisseria meningitidis* requires a functional interplay between

the focal adhesion kinase, Src and cortactin. PLoS One 2012;7:e39613.

8. Hill DJ, Griffiths NJ, Borodina E, et al. Cellular and molecular biology of *Neisseria meningitidis* colonization and invasive disease. Clin Sci (Lond) 2010;118:547-64.

9. Pizza M, Rappuoli R. *Neisseria meningitidis*: pathogenesis and immunity. Curr Opin Microbiol 2015;23:68-72.

10. Schoen C, Kischkies L, Elias J, et al. Metabolism and virulence in *Neisseria meningitidis*. Front Cell Infect Microbiol 2014;4:114.

11. Coureuil M, Lecuyer H, Bourdoulous S, et al. A journey into the brain: insight into how bacterial pathogens cross blood-brain barriers. Nat Rev Microbiol 2017;15:149-59.

12. Frasch CE, Bash MC. *Neisseria meningitidis* vaccines. In: Ellis RW, Brodeur BR, editors. New Bacterial Vaccines. Canada: Springer; 2003. p. 229-43.

13. Pinto VB, Burden R, Wagner A, et al. The development of an experimental multiple serogroups vaccine for *Neisseria meningitidis*. PLoS One 2013;8:e79304.

14. Ali A, Jafri RZ, Messonnier N, et al. Global practices of meningococcal vaccine use and impact on invasive disease. Pathog Glob Health 2014;108:11-20.

15. Gasparini R, Panatto D, Bragazzi NL, et al. How the Knowledge of Interactions between *Meningococcus* and the Human Immune System Has Been Used to Prepare Effective *Neisseria meningitidis* Vaccines. J Immunol Res 2015;2015:189153.

16. Cotter SE, Surana NK, St Geme JW, 3rd. Trimeric autotransporters: a distinct subfamily of autotransporter proteins. Trends Microbiol 2005;13:199-205.

17. Linke D, Riess T, Autenrieth IB, et al. Trimeric autotransporter adhesins: variable structure, common function. Trends Microbiol 2006;14:264-70.

18. Comanducci M, Bambini S, Brunelli B, et al. NadA, a novel vaccine candidate of *Neisseria meningitidis*. J Exp Med 2002;195:1445-54.

19. Bambini S, Muzzi A, Olcen P, et al. Distribution and genetic variability of three vaccine components in a panel of strains representative of the diversity of serogroup B meningococcus. Vaccine 2009;27:2794-803.

20. Findlow J, Borrow R, Snape MD, et al. Multicenter, open-label, randomized phase II controlled trial of an investigational

recombinant Meningococcal serogroup B vaccine with and without outer membrane vesicles, administered in infancy. Clin Infect Dis 2010;51:1127-37.

21. Litt DJ, Savino S, Beddek A, et al. Putative vaccine antigens from *Neisseria meningitidis* recognized by serum antibodies of young children convalescing after meningococcal disease. J Infect Dis 2004;190:1488-97.

22. Vogel U, Taha MK, Vazquez JA, et al. Predicted strain coverage of a meningococcal multicomponent vaccine (4CMenB) in Europe: a qualitative and quantitative assessment. Lancet Infect Dis 2013;13:416-25.

23. Wang X, Cohn A, Comanducci M, et al. Prevalence and genetic diversity of candidate vaccine antigens among invasive *Neisseria meningitidis* isolates in the United States. Vaccine 2011;29:4739-44.

24. Comanducci M, Bambini S, Caugant DA, et al. NadA diversity and carriage in *Neisseria meningitidis*. Infect Immun 2004;72:4217-23.

25. Schielke S, Huebner C, Spatz C, et al. Expression of the meningococcal adhesin NadA is controlled by a transcriptional regulator of the MarR family. Mol Microbiol 2009;72:1054-67.

26. Fagnocchi L, Biolchi A, Ferlicca F, et al. Transcriptional regulation of the nadA gene in *Neisseria meningitidis* impacts the prediction of coverage of a multicomponent meningococcal serogroup B vaccine. Infect Immun 2013;81:560-9.

27. Petrey D, Honig B. Protein structure prediction: inroads to biology. Mol Cell 2005;20:811-9.

28. Saeidnia S, Manayi A, Abdollahi M. The pros and cons of the in-silico pharmaco-toxicology in drug discovery and development. Int J Pharm 2013;9:176-81.

29. Simossis VA, Heringa J. PRALINE: a multiple sequence alignment toolbox that integrates homology-extended and secondary structure information. Nucleic Acids Res 2005;33:W289-94.

30. Gasteiger E, Hoogland C, Gattiker A. Protein Identification and Analysis Tools on the ExPASy Server. In: Walker JM, editor. The Proteomics Protocols Handbook 2005. p. 571-607.

31. Viklund H, Bernsel A, Skwark M, et al. SPOCTOPUS: a combined predictor of signal peptides and membrane protein topology. Bioinformatics 2008;24:2928-9.

32. Kelley LA, Sternberg MJ. Protein structure prediction on the Web: a case study using the Phyre server. Nat Protoc

2009;4:363-71.

33. Wiederstein M, Sippl MJ. ProSA-web: interactive web service for the recognition of errors in three-dimensional structures of proteins. *Nucleic Acids Res* 2007;35:W407-10.

34. Lovell SC, Davis IW, Arendall WB, 3rd, et al. Structure validation by Calpha geometry: phi,psi and Cbeta deviation. *Proteins* 2003;50:437-50.

35. Xu D, Zhang Y. Improving the physical realism and

structural accuracy of protein models by a two-step atomic-level energy minimization. *Biophys J* 2011;101:2525-34.

36. Berezin C, Glaser F, Rosenberg J, et al. ConSeq: the identification of functionally and structurally important residues in protein sequences. *Bioinformatics* 2017;20:1322-4.

37. Saxena A, Sangwan RS, Mishra S. Fundamentals of Homology Modeling Steps and Comparison among Important Bioinformatics Tools: An Overview *Sci Int* 2013;1:237-52.